



# HP2-T23<sup>Q&As</sup>

Supporting Industry Standard Server Solutions

**Pass HP HP2-T23 Exam with 100% Guarantee**

Free Download Real Questions & Answers **PDF** and **VCE** file from:

<https://www.pass4itsure.com/hp2-t23.html>

100% Passing Guarantee  
100% Money Back Assurance

Following Questions and Answers are all new published by HP Official Exam Center

-  **Instant Download** After Purchase
-  **100% Money Back** Guarantee
-  **365 Days** Free Update
-  **800,000+** Satisfied Customers



**QUESTION 1**

After you replace the system board in a ProLiantBL460c G8 server blade,the server cannot conned to an external shared storage through the SAS interface. Other similar servers in the same enclosure are in working condition. What should you check to verify that the physical hardware connectivity it connected?

- A. External storage power status
- B. ACU of the server blade for storage status
- C. Server bladeiLO tot hardware information detected by the management processor
- D. Server blade port mapping for theIOModule connectivity to the interconnect module

Correct Answer: D

---

**QUESTION 2**

What should be installed on a ProLiant Gen8 server to display operating system information within the iLO 4 GUI?

- A. System Management Home Page
- B. HP Management Agents
- C. Agentless Management Service
- D. ProLiant Support Pack

Correct Answer: C

---

**QUESTION 3**

What should be run in the Virtual Connect Support Utility (VCSU) before initiating a Virtual Connect firmware upgrade?

- A. Show all
- B. VC Support Dump
- C. Health Check
- D. Show Config

Correct Answer: C

---

**QUESTION 4**

A customer has a ProLiant DL32Ce Gen8 server with a Smart Array B120i controller installed The customer wants to migrate from RAID 5 to RAID 6 for increased fault tolerance RAID 6 is not listed as an option in the ACU.



What is the most likely reason that RAID 6 is not an option?

- A. The Smart Array B120i controller does not offer RAID 6
- B. The controller firmware must be upgraded
- C. The Smart Array Advanced Pack must be purchased
- D. The Smart Array BIOS is configured incorrectly

Correct Answer: A

---

#### QUESTION 5

Microsoft Windows BitLocker Encryption feature uses a TPM microcontroller chip to store certificates and encryption keys on a DL380 G7.

Which action must a field engineer perform before upgrading server firmware and installing an additional storage controller?

- A. Create new certificates and encryption keys.
- B. Disable BitLocker.
- C. Delete certificates and encryption keys.
- D. Disable TPM.

Correct Answer: B

[Latest HP2-T23 Dumps](#)

[HP2-T23 Practice Test](#)

[HP2-T23 Exam Questions](#)